

BID TABS
 PROJECT 18-1413 PETZKE PARK PLAYGROUND LIGHTING
 BID DATE: SEPTEMBER 5, 2018

Item Number	Description	Quantity	Unit	Unit Price	Total	Unit Price	Total	Unit Price	Total
628.7010	Inlet Protection, Type B	2	EACH		\$0.00		\$0.00		\$0.00
652.0110	Conduit Rigid Metallic 1-Inch	55	LF		\$0.00		\$0.00		\$0.00
652.0210	Conduit Rigid Nonmetallic Schedule 40 1-Inch	945	LF		\$0.00		\$0.00		\$0.00
654.0105	Concrete Bases Type 5 (Lighting)	5	EACH		\$0.00		\$0.00		\$0.00
655.0610	Electrical Wire Lighting 12 AWG (5 Wires)	2400	LF		\$0.00		\$0.00		\$0.00
656.0615	Electrical Wire Lighting 10 AWG (5 Wires)	700	LF		\$0.00		\$0.00		\$0.00
671.0200	Conduit HDPE Directional Bore 1-Duct 1-1/4 Inch (Only 1-In needed)	260	LF		\$0.00		\$0.00		\$0.00
SPV.0060.01	Site Lighting (Pole, Luminaire, All #12 AWG Wire within Each Pole)	5	EACH		\$0.00		\$0.00		\$0.00
SPV.0060.02	Install MILBANK Junction Box (12" x 12" x 6") w/Cover and L-com Pole Mounting Kit	5	EACH		\$0.00		\$0.00		\$0.00
SPV.0060.03	Install Waterproof Quazite PC Underground Enclosure (8.5"L x 6.5"W x 6"H)	1	EACH		\$0.00		\$0.00		\$0.00
SPV.0090.01	Fiber Optic Cable (Hitachi Cable, 6 Fibers, Type OM2 (61347-6)) Leave Blank	1600	LF		\$0.00		\$0.00		\$0.00
SPV.0105.01	Lighting Connection (Includes all Breakers and Hardware at Panel)	1	LS		\$0.00		\$0.00		\$0.00
SPV.0105.02	Restoration (4 Inches Topsoil, Seed and Fertilizer)	1	LS		\$0.00		\$0.00		\$0.00
	Bid Total				\$0.00		\$0.00		\$0.00
NO BIDS RECEIVED									